The PDEQ^{*} Virtual Septic Inspection

CLICK ANYWHERE on THIS PAGE to return to U.S. SEPTIC AUTHORITIES & DESIGN SPECIFICATIONS at InspectApedia.com



* Pima County Department of Environmental Quality

Use this step-by-step guide to learn what PDEQ inspectors are looking for Inspection criteria are highlighted so you know what to expect Additional questions? Call and ask to speak with an inspector: 520-724-7400

The following slides will illustrate how to:

Schedule your inspection Help the inspector find your jobsite Ensure you provide the correct paperwork



To Schedule An Inspection For <u>Non-remote</u> Areas

 Use the Interactive Voice Response (IVR) System

Call 520-724-6970 by 4:00 pm for an inspection the following business day
Have the 10-digit activity number available
The 5-digit septic inspection code is 03060

To Schedule An Inspection For A <u>Remote</u> Area

 Remote areas include: Ajo, Why, Lukeville, Arivaca, Sasabe, Redington and Mt. Lemmon
 Call <u>PDEQ</u> at least 48 hours in advance to schedule inspection 520-724-7400



Post the address at the jobsite



Put the paperwork in a location that is easy for the inspector to find





What Paperwork Should Be At The Jobsite?

Many inspections are rejected because the necessary paperwork is not at the jobsite Continue with the Virtual Inspection to find out what paperwork must be provided at the time of your requested inspection

Required Paperwork 1 of 4

POST AT JOB SITE Checklist

Provide the required paperwork in a visible location at the jobsite

<u>11(51 E</u>		REJECTED IF No	<u>OTTOSTED</u>
PED DC 18 83 050 A1		MUST RE POSTE	D PRIOR TO INSPECT
· · ·			B
<50 foot from the second	<u>Residential</u>	yed on the building. yed a minimum of 36"	Entrance numbers shall be 12"
<50 feet from the cur >50 feet from the cur	b requires 3" numbers display	ved a minimum of 36"	Building numbers shall be 6"
above the ground at	the primary access point.	yea a minimum of 50	Space numbers shall be 3"
CHAME	BER SEPTIC SY	YSTEM FINAL	INSPECTION
Property Address:		Project Number:	
Inspector Name:		Date of Inspectio	on:
	all be performed, and	l the certificate shall b	e completed PRIOR to the ca
Septic Tank and Distributio	on Box: R18-9-A314		
Tank leak tested (comp		led)	
Tank size and location			s-built
Manufacturer, tank size	max depth of cover.	and date of manufactu	re marked on top of tank
Mfr.			
Tank is level			
Inlet & Outlet clearly a	nd permanently marke	d above or to the right	or left of openings
Inlet/outlet openings an	d vertical leg at least	4" but not smaller than	size of connecting sewer
a. Extends at least 4"	above & at least 12"	below liquid surface	
	ed 2" above outlet inv		
Two compartments, or			
Appropriate risers insta			ches
Access openings at leas		0	
a One over inlet on	e over outlet		
b. If first compartme	nt is over 12 feet long	, 3rd opening provided	over baffle
Appropriate baffle in pl	ace OR		
No baffle for t	anks in series		
Effluent filter installed	and is accessible		
Pipe between septic tan	k and distribution box	placed on natural grou	and or compacted fill
Distribution box level,	on stable surface, and	inlet at least 1" above	outlet
Plumbing and distributi	on piping is appropria	te size / material and c	onnections water tight
Chambers: R18-9-E302			
Trenches located accord	ding to site plan		
Trench spacing: Dista	ince:		Depth:
Number of trenches:	Dimensions: Leng	th: Width:	Depth:
Number of chambers pe	er trench:		·
Minimum 9 inches avai	lable over chamber fo	r cover	
Chamber end plates left	t off for inspection		
Chambers follow conto			and debris
Observation port(s) inst	alled above grade and	capped	
Proper drainage on prop	perty to minimize dam	age from flooding and	erosion
Verification of General Per			
Accurate "As-Built" sit	e plan signed by the fi	eiu inspector	
Comments:			

Required
 Paperwork
 2 of 4

 Certificate of Watertightness (must be completely filled out PRIOR to inspection)

	of Watertightness of an Installed Septic Tan Determined by Field Watertightness Testing Under Arizona Administrative Code R18-9-A309(C) (1)
Project Informat	ion
Property Address:	
File Number:	
Watertightness T	ester
Name:	
Septic Tank Info	rmation
Manufacturer:	
Design Liquid Cap	pacity: gallons
Was a Manufactur R18-9-A314 rece	er's Certificate of Conformance stating that tank meets the requirements of ived from manufacturer? Yes No No
Was a Manufactur R18-9-A314 rece Watertightness T	ived from manufacturer? Yes No No
R18-9-A314 receit	ived from manufacturer? Yes No No C
R18-9-A314 recei	ived from manufacturer? Yes No No Constraints No Co
R18-9-A314 rece: Watertightness T 1. Start 24-hour pr 2. Start of field wat 3. End of field wat (no water drop Passed watertig Passed watertig	ived from manufacturer? Yes No No C
R18-9-A314 rece: Watertightness T 1. Start 24-hour pr 2. Start of field wa Date: Date:	ived from manufacturer? Yes No No Constraints No Co
R18-9-A314 rece: Watertightness T 1. Start 24-hour pr 2. Start of field wa 2. Start of field wa 2. Start of field wa 2. Passed watertight 1. Indicate Repairs Certification 1 have tested the in watertightness test certify that the sep	ived from manufacturer? Yes No No Constraints No Co

Note: Not required for projects with a Notice of Intent dated 11-12-05 or before



To help you correctly fill out the Certificate of Watertightness, follow the instructions to the right

If you still have questions, contact an inspector (see slide #2 for phone number)

How to conduct a watertightness test: (Arizona Administrative Code R18-9-A314.5.d)

Fill the septic tank to the outlet.

Once filled, note the date and time on the Certificate of Watertightness on line 1 (see example below).

Allow the tank to soak for 24 hours.

After 24 hours has passed, refill the tank to the outlet and make a note of the water level. Fill in the date and time on line 2 (see example). This is the start of the field watertightness test.

After 1 hour has elapsed, look at the water level again. Fill in the date and time on line 3 (see example). This is the end of the field watertightness test.

Check the appropriate box indicating whether the tank passed the watertightness test without repair or if it passed the watertightness test following repair. NOTE: The tank passes if the water level does not drop over the one-hour period.

Be sure the rest of the information, including the signature of the tester, is filled in on the Certificate of Watertightness of an Installed Septic Tank.

EXAMPLE:

Watertightness Test Information

- 1. Start 24-hour presoak with clean water
- 2. Start of field watertightness test
- 3. End of field watertightness test

<u>Date</u>	<u>Time</u>
2-10-07	9:00am
2-11-07	9:00am
2-11-07	10:00am

□ Passed watertightness test without repair

(no water drop over 1-hour period per A.A.C. R18-9-A314(5)(d)(ii))

□ Passed watertightness test following repair

Indicate Repairs Made:

Required Paperwork 3 of 4 Construction Authorization (Form C) – needs to be the original copy provided in the inspection packet

PIMA COUNTY DEPARTMENT OF ENVIRONMENTAL QUALITY CONSTRUCTION AUTHORIZATION FOR AN ONSITE WASTEWATER TREATMENT FACILITY TYPE 4.02 THROUGH 4.22 GENERAL PERMITS

Property Address: 1234 N. EASY ST.

Applicant Information:		File Number: P07CP00000	
Name:	JOHN Ç	. PUBLIC	Permitted Design Flow: 600 Gallons Per Day
Address:		. PARK ST. N, AZ 85777	Manufactured/mobile Site built (SFR) Number of Bedrooms 3 Number of Fixture Units 37
Name and Address of Facility (if different from above):		lity (if different from above):	County: Pima Parcel No: 000-00-000R
Characteristics of the Wastewater Source(s): √ Typical sewage from a single family residence □ Typical sewage from multiple residences □ Sewage source(s) other than residential:		T 00S R 00E S 00 SW ¼ (000) SE ¼ (00) SW ¼ (00)	
		Latitude: 00° 00' 17" N Longitude: 000° 00' 00" W	
Design Documents That Are The Basis For The Authorization: √ Notice of Intent, dated 3/1/07 √ Site Investigation, dated 1/1/07 √ Site plan, dated 1/1/07 √ List of Materials, dated 1/1/07 √ Design plan, dated 1/1/07 √ Soil Evaluation results, dated 1/1/07 □ Operation and Maintenance Plan, dated □ Other document(s) √ Appropriate Fee			

Construction Authorization Stipulations: This Construction Authorization is issued in accordance with the Arizona Administrative Code Title 18, Chapter 9, Article 3. The applicant is authorized to construct the facility at the location specified herein based on the listed design documents under the terms and conditions of the checked General Permit number(s) and the requirements of Arizona Revised Statutes Title 49, Chapter 2. The Applicant has two years from the approval date of this document to complete construction and submit the Request for Discharge Authorization form and any additional required documents specified in A.A.C. R18-9-A309(C) or the checked General Permits. Construction shall conform to the approved design documents. A County Inspector shall perform the final inspection of the system and submit the results to Development Services for issuance of a Discharge Authorization.

Title Date

Signature Design Criteria

Tank Size Required: 1250 Gals. Soil Absorption Rate (SAR): 0.60gpd/Sq.Ft Distribution Boxes: 1

Effective Absorption Area Required: 1000 Sq. Ft Absorption Area per Chamber: 28.38 Sq.Ft.

Number of Trenches: 2 Trench Length: 72' Trench Depth: 6.5'(MAX) Trench Width: 3'

Number of Chambers per Trench: 18

Total Number of Chambers Required: 36

Required Paperwork 4 of 4 Site Plan - needs to be the <u>original</u> plan with any As-built changes noted

APPROVAL FOR CONSTRUCTION DEPARTMENT OF ENVIRONMENTAL QUALITY DATE 01-01-07 BY

Proposed 1250 gallon septic tank

> 2 trenches, 14 chambers each trench

> > Proposed 2bdrm mobile home

As-Built Plan



The As-Built Plan should be an accurate reflection of what the installed system looks like. Major changes, such as relocating the trenches, require a revision through Development Services PRIOR TO INSPECTION. Even minor changes (i.e. the pipes exit the D-box on the middle and left sides instead of on the right and left) should be drawn in. What inspectors see in the ground must be reflected on the As-Built Plan.

Construction Authorization

- Look on the Construction Authorization (Form C) for important design and installation criteria
 - Tank size
 - Trench depth (Form C often sets minimum and maximum depths – stay within limits or contact the designer and Development Services for a revision)
 - Number of chambers per trench
 - Number of trenches
 - Type of chamber (High Capacity vs. Quick4 Standard)

Get A Revision From Development Services If...

You install a different type of chamber than indicated on the Construction Authorization (i.e. the Construction Authorization calls for High Capacity chambers - 6.25' in length, and you install Quick4 Standard chambers – 4' in length)



Get A Revision From Development Services If...

You install an aggregate/trench (perforated pipe) system when a chamber system is called for on the Construction Authorization





Effective 10/01/2007 Conventional Septic Inspections will cost \$130 (per inspection)

The fee for the first inspection is included when you pay for your Permit at Development Services.

 All additional inspections will cost \$130 each, including partials.

Remember, this may affect your final cost.

- Clean off the top of the tank so that tank specs can be seen:
 - Manufacturer's name
 - Tank size
 - Date of manufacture
 - Maximum depth of cover
 - "Inlet" and "Outlet" (marked on the top or sides)




Septic Tank

Leave both access openings/manholes open for inspection



 Ensure that the septic tank is level




Inlet:

The sanitary 'T' needs to extend 4 inches above and 12 inches below the water surface; should be accessible from the manhole

Outlet:

An effluent filter (with the arrow pointing toward the outlet) must be installed; should be accessible from the manhole





Access to the manholes needs to be within 6 inches of finished grade. Install risers if necessary to make this possible.





Ensure the pipe between the tank and the D-box is supported by natural ground or compacted fill



The D-box/junction box Ensure the Dbox/junction box: is level is on a stable surface is installed so that the inlet is at least 1 inch above the outlet(s)

Trenches - Spacing Needs to be a minimum of 5 feet Must meet or exceed the spacing on the approved As-built plan Measured between nearest sidewalls



Trenches

Must be located according to the site plan (note minor changes on the As-Built Plan; initial and date the change) Need to follow the contour of the land





Trenches – Depth of Cover

Thin-walled pipe may be used if there is LESS than 2 feet of cover over the disposal pipe (connecting the tank to the D-box to the chambers)



Photo shows thin-walled pipes

Trenches – Depth of Cover

SDR 35 or equivalent pipe MUST be installed if there is MORE than 2 feet of cover over the disposal pipe (connecting the tank to the D-box to the chambers)




Photos show SDR 35 pipes



Cover Over Chambers

Allow <u>at least</u> 9 inches over the chambers for cover The Construction Authorization (Form C) often sets minimum and maximum depths – stay within limits or contact the designer and **Development Services** for a revision



Chamber Installation

Chambers may curve 10° in either direction at each joint without using an elbow

Ensure the chambers follow the contour of the land

Rake the bottom of the trench so that it is free of rocks and debris






Chamber End Plates

Leave the chamber ends plates OFF for the inspection

This is so the inspector can see the bottom of the trench



Observation Ports

- Need to be capped
- Ensure there are no perforations (holes) <u>above</u> grade
- Stabilize ports when backfilling to ensure they are straight
- Perforate <u>below</u> grade or install a coupler to keep it from going to the bottom of the trench



Common Installation Mistakes

 The following slides show mistakes that PDEQ inspectors commonly see in the field





Pipes in the distribution/ junction box overlap This prevents effluent from being evenly distributed



 The pipe from the tank to the
 D-box is not supported by soil
 The pipe could collapse when backfilled



 Tank lids are not removed for the inspection
 Inspectors cannot verify the presence of the sanitary 'T' or the effluent filter



Tank is not filled and the watertightness paperwork is not completed at the time of the inspection



Perforations (holes) in the observation port are present above grade This can contribute to disease-carrying organisms



 Observation ports are not capped
 This can contribute to disease-carrying organisms

Online

https://webcms.pima.gov/government/environmental_quality/



What's new? Forms Regulations Checklists Links Contact information

Contact

Pima County Department of Environmental Quality

> 33 N. Stone, 7th floor Tucson, Arizona 85701 520-724-7400

https://webcms.pima.gov/government/environmental_ quality/